DIPLOMA IN CIVIL ENGINEERING (DCLEG)

Term-End Examination December, 2013

BCE-062 : CONSTRUCTION SUPERVISION AND BUILDING MAINTENANCE

Note: Question number 1 is compulsory. Attempt any four from the remaining questions.

- 1. (a) Write True or False(T/F) for the following 7 statements.
 - (i) curing of concrete is not desired in coastal areas.
 - (ii) PVC pipes can not sustain high pressures. That is why these should not be used for pumping water to over head tanks.
 - (iii) Good quality marble absorbs only a little quantity of water.
 - (iv) Reinforcement provides ductility to Reinforced cement concrete.
 - (v) There may be defects in timbers due to natural agents.
 - (vi) Cast iron is better suited than mild steel for drainage of water.
 - (vii) Log book for an equipment is an important document.

(b) Match the following: 7 (i) Sap stain defect (A) Steel Corrosion Moisture in timber (B) (ii) Foundation (C) Soil (iii) (iv) Honey combing (D) Concrete Cup shake (E) Material record (\mathbf{v}) (vi) Direct (F) Cost (vii) Document (G) Timber What are the duties of a construction 2. (a) 7 supervisor? Explain briefly. (b) Briefly describe a method to show the 7 progress of a construction projects. 3. (a) List out the documents/registers to be 7 maintained in store and explain the procedure of daily receipts and issue of stores briefly. Discuss the importance of curing of (b) 7 concrete briefly. 4. (a) Do we do Anti termite treatment for 7 building structure? If yes, briefly discuss a method in this respect. (b) What precautions can be taken to reduce 7 the number of accidents at a construction

site?

- 5. (a) Differentiate between GI and PVC pipes and explain how they are graded or classified from use and quality point of view?
 - (b) Compare direct and indirect costs of a 7 construction project.
- **6**. Explain, stepwise, any two of the following. 2x7=14
 - (a) Laying of terrazo flooring
 - (b) Tiling in bathroom walls
 - (c) Repairs in concealed water piping.
- 7. Write short notes on any two of the following 2x7=14
 - (a) Water proofing of cieling slab
 - (b) Repair of marble flooring
 - (c) Training of Labour at site.